



NOTES:

1. Brass risers, nipples, couplings and elbows shall be Schedule 40.
2. Entire assembly above ground shall be painted with one prime coat and two green enamel finish coats.
3. No take-offs shall be made between the water meter and the backflow preventer.

Dimensions are in millimeters, except as noted

REVISIONS NO. DATE		CITY OF LONG BEACH, CALIFORNIA DEPARTMENT OF PUBLIC WORKS	STANDARD PLAN NO.
1 12/10/97 2 12/23/02 3 4	BACKFLOW PREVENTER INSTALLATION 100 mm (4") AND UNDER LINE SIZE		
APPROVED BY: <i>Mark Duffler</i> CITY ENGINEER R.E. No. 40589		DATE: 1/10/03 EX. DATE: 03/31/03	SHEET 1 OF 1