DRAFT ENVIRONMENTAL IMPACT REPORT

ALAMITOS BAY MARINA REHABILITATION PROJECT SCH NO. 2008041028

Submitted to:

City of Long Beach Department of Development Services 333 West Ocean Boulevard, 5th Floor Long Beach, California 90802

Prepared by:

LSA Associates, Inc. 20 Executive Park, Suite 200 Irvine, California 92614-4731 (949) 553-0666



October 2009

TABLE OF CONTENTS

1.0	EXE	CUTIVE SUMMARY	1-1
	1.1	INTRODUCTION	1-1
	1.2	SUMMARY OF PROJECT DESCRIPTION	1-1
	1.3	ALTERNATIVES	1-2
	1.4	AREAS OF CONTROVERSY	
	1.5	SUMMARY OF IMPACTS AND MITIGATION MEASURES	1-4
2.0	INTR	ODUCTION	
	2.1	PURPOSE AND TYPE OF EIR/INTENDED USES OF EIR	2-2
	2.2	NOTICE OF PREPARATION AND AREAS OF CONTROVERSY.	2-3
	2.3	EFFECTS FOUND NOT TO BE SIGNIFICANT	2-4
	2.4	FORMAT OF THE EIR	2-5
	2.5	INCORPORATION BY REFERENCE	2-7
3.0	PROJ	IECT DESCRIPTION	3-1
	3.1	PROJECT LOCATION AND SITE DESCRIPTION	3-1
	3.2	PROJECT HISTORY AND BACKGROUND	3-2
	3.3	PROJECT GOALS AND OBJECTIVES	3-4
	3.4	PROJECT CHARACTERISTICS	3-5
	3.5	PROJECT PHASING	3-10
	3.6	DISCRETIONARY PERMITS, APPROVALS, OR ACTIONS	
		REQUIRED	3-10
4.0	EXIS	TING ENVIRONMENTAL SETTING, IMPACTS, AND	
	MITI	GATION MEASURES	4-1
4.1	AES	THETICS	
	4.1.1	EXISTING ENVIRONMENTAL SETTING	4.1-1
	4.1.2	REGULATORY SETTING	4.1-5
	4.1.3	METHODOLOGY	4.1-6
	4.1.4	THRESHOLDS OF SIGNIFICANCE	4.1-7
	4.1.5	IMPACTS AND MITIGATION MEASURES	4.1-8
	4.1.6	MITIGATION MEASURE	4.1-19
	4.1.7	CUMULATIVE IMPACTS	4.1-19
	4.1.8	SIGNIFICANT UNAVOIDABLE ADVERSE IMPACTS	4.1-20
4.2	AIR (QUALITY	4.2-1
	4.2.1	EXISTING ENVIRONMENTAL SETTING	4.2-1
	4.2.2	REGULATORY SETTING	4.2-16
	4.2.3	METHODOLOGY	4.2-27
	4.2.4	THRESHOLDS OF SIGNIFICANCE	4.2-27
	4.2.5	STANDARD CONDITIONS	4.2-32
	4.2.6	IMPACTS AND MITIGATION MEASURES	4.2-32
	4.2.7	MITIGATION MEASURES	4.2-38

	4.2.8	CUMULATIVE IMPACTS	
	4.2.9	SIGNIFICANT UNAVOIDABLE ADVERSE IMPACTS	4.2-43
4.3	BIOL	OGICAL RESOURCES	4.3-1
	4.3.1	EXISTING ENVIRONMENTAL SETTING	4.3-1
	4.3.2	REGULATORY SETTING	4.3-11
	4.3.3	METHODOLOGY	
	4.3.4	THRESHOLDS OF SIGNIFICANCE	4.3-16
	4.3.5	POTENTIALLY SIGNIFICANT IMPACTS AND MITIGATION	
		MEASURES	
	4.3.6	MITIGATION MEASURES	
	4.3.7	CUMULATIVE IMPACTS	
	4.3.8	SIGNIFICANT UNAVOIDABLE ADVERSE IMPACTS	
4.4		ΓURAL AND HISTORIC RESOURCES	
	4.4.1	EXISTING ENVIRONMENTAL SETTING	
	4.4.2	METHODOLOGY	
	4.4.3	THRESHOLDS OF SIGNIFICANCE	
	4.4.4	IMPACTS AND MITIGATION MEASURES	
	4.4.5	CUMULATIVE IMPACTS	
	4.4.6	SIGNIFICANT UNAVOIDABLE ADVERSE IMPACTS	
4.5		LOGY AND SOILS	
	4.5.1	EXISTING ENVIRONMENTAL SETTING	
	4.5.2	METHODOLOGY	
	4.5.3	THRESHOLDS OF SIGNIFICANCE	
	4.5.4	IMPACTS AND MITIGATION MEASURES	
	4.5.5	CUMULATIVE IMPACTS	
	4.5.6	LEVEL OF SIGNIFICANCE AFTER MITIGATION	
4.6		ARDS AND HAZARDOUS MATERIALS	
	4.6.1	EXISTING ENVIRONMENTAL SETTING	
	4.6.2	REGULATORY SETTING	
	4.6.3	METHODOLOGY	
	4.6.4	THRESHOLDS OF SIGNIFICANCE	
	4.6.5	IMPACTS AND MITIGATION MEASURES	
	4.6.6	MITIGATION MEASURES	
	4.6.7	CUMULATIVE IMPACTS	
	4.6.8	SIGNIFICANT UNAVOIDABLE ADVERSE IMPACTS	
4.7		ROLOGY AND WATER QUALITY	
	4.7.1	EXISTING SETTING	
	4.7.2	REGULATORY SETTING	
	4.7.3	THRESHOLDS OF SIGNIFICANCE	
	4.7.4	IMPACTS AND MITIGATION	
	4.7.5	MITIGATION MEASURES	
	4.7.6	CUMULATIVE IMPACTS	
	4.7.7	SIGNIFICANT UNAVOIDABLE ADVERSE IMPACTS	4.7-32

4.8	LAND	O USE	4.8-1
	4.8.1	EXISTING ENVIRONMENTAL SETTING	4.8-1
	4.8.2	REGULATORY SETTING	4.8-2
	4.8.3	METHODOLOGY	
	4.8.4	THRESHOLDS OF SIGNIFICANCE	4.8-9
	4.8.5	IMPACTS AND MITIGATION MEASURES	4.8-10
	4.8.6	CUMULATIVE IMPACTS	4.8-32
	4.8.7	SIGNIFICANT UNAVOIDABLE ADVERSE IMPACTS	4.8-33
4.9	NOIS	E	4.9-1
	4.9.1	EXISTING ENVIRONMENTAL SETTING	4.9-1
	4.9.2	REGULATORY SETTING	4.9-4
	4.9.3	METHODOLOGY	
	4.9.4	THRESHOLDS OF SIGNIFICANCE	
	4.9.5	IMPACTS AND MITIGATION MEASURES	4.9-6
	4.9.6	MITIGATION MEASURES	4.9-11
	4.9.7	CUMULATIVE IMPACTS	
	4.9.8	SIGNIFICANT UNAVOIDABLE ADVERSE IMPACTS	4.9-13
4.10	PUBL	IC SERVICES AND UTILITIES	
	4.10.1	EXISTING ENVIRONMENTAL SETTING	4.10-1
	4.10.2	METHODOLOGY	
	4.10.3	THRESHOLDS OF SIGNIFICANCE	
	4.10.4	IMPACTS AND MITIGATION MEASURES	4.10-9
	4.10.5	MITIGATION MEASURES	4.10-14
	4.10.6	CUMULATIVE IMPACTS	
	4.10.7	SIGNIFICANT UNAVOIDABLE ADVERSE IMPACTS	
4.11	RECR	EATION	
	4.11.1	EXISTING ENVIRONMENTAL SETTING	
	4.11.2	REGULATORY SETTING	
	4.11.3	METHODOLOGY	
	4.11.4	THRESHOLDS OF SIGNIFICANCE	4.11-5
	4.11.5	IMPACTS AND MITIGATION MEASURES	
	4.11.6	CUMULATIVE IMPACTS	
	4.11.7	SIGNIFICANT UNAVOIDABLE ADVERSE IMPACTS	
4.12	TRAN	SPORTATION AND CIRCULATION	
	4.12.1	EXISTING ENVIRONMENTAL SETTING	
	4.12.2	METHODOLOGY	
	4.12.3	THRESHOLDS OF SIGNIFICANCE	
	4.12.4	IMPACTS AND MITIGATION MEASURES	
	4.12.5	MITIGATION MEASURES	
	4.12.6	CUMULATIVE IMPACTS	
	4.12.7	LEVEL OF SIGNIFICANCE AFTER MITIGATION	
5.0		RNATIVES	
	5 1	SELECTION OF ALTERNATIVES	5-2

	5.2	ALTERNATIVES CONSIDERED BUT REJECTED	5-3
	5.3	PROPOSED PROJECT	
	5.4	PROJECT GOALS AND OBJECTIVES	5-8
	5.5	ALTERNATIVE 1: NO PROJECT/NO DEVELOPMENT	5-9
	5.6	ALTERNATIVE 2: REDUCED PROJECT ALTERNATIVE	5-11
	5.7	ALTERNATIVE 3: ON-SITE DRY STACK STORAGE	
		ALTERNATIVE	5-18
	5.8	IDENTIFICATION OF ENVIRONMENTALLY SUPERIOR	
		ALTERNATIVE	5-25
6.0	LON	G-TERM IMPLICATIONS OF THE PROJECT	6-1
	6.1	SIGNIFICANT IRREVERSIBLE ENVIRONMENTAL CHANGES	6-1
	6.2	GROWTH-INDUCING IMPACTS	
7.0	MIT	IGATION MONITORING AND REPORTING PROGRAM	7-1
	7.1	MITIGATION MONITORING REQUIREMENTS	7-1
	7.2	MITIGATION MONITORING PROCEDURES	7-2
8.0	LIST	OF PREPARERS	8-1
	8.1	LSA ASSOCIATES, INC. STAFF	8-1
	8.2	CITY STAFF	8-1
	8.3	TECHNICAL CONSULTANTS	8-1
9.0	REF	ERENCES	9-1

APPENDICES

- A: NOTICE OF PREPARATION (NOP), NOP COMMENTS, AND SCOPING MEETING COMMENTS
- **B: AIR QUALITY CALCULATIONS**
- C: MARINE BIOLOGY REPORTS AND NESTING BIRD SURVEYS
- D: CULTURAL/HISTORIC RESOURCES REPORT
- **E: GEOTECHNICAL EVALUATION**
- F: TIER III SEDIMENT CHARACTERIZATION, SUPPLEMENTAL SAMPLING AND ANALYSIS REPORT, AND BEST MANAGEMENT PRACTICES
- G: FIRST SEARCH ENVIRONMENTAL DATABASE REPORT
- H: ALAMITOS BAY MARINA MASTER PLAN
- I: NOISE STUDY DATA
- J: TRAFFIC IMPACT ANALYSIS

FIGURES AND TABLES

FIGURES

Figure 3.1: Project Location	3-13
Figure 3.2: Key View Locations	3-14
Figure 3.3: Dredging Limits Basin 1	3-15
Figure 3.4: Dredging Limits Basin 2	3-16
Figure 3.5: Dredging Limits Basin 3	
Figure 3.6: Dredging Limits Basin 4	3-18
Figure 3.7: Dredging Limits Basin 5	3-19
Figure 3.8: Dredging Limits Basin 6-North	3-20
Figure 3.9: Dredging Limits Basin 6-South	3-21
Figure 3.10: Dredging Limits Basin 7	3-22
Figure 3.11: Restroom Locations	
Figure 3.12: Typical Seawall Repair Cross-Section	3-24
Figure 3.13: Proposed Dock Layout Over Existing Dock Layout	3-25
Figure 3.14: Temporary/Long Dock Configuration	
Figure 3.15: Proposed Open Space/Habitat Mitigation Site	
Figure 3.16: Preliminary Phasing Plan	3-28
Figure 4.1.1: Key View Locations Map	
Figure 4.1.2: Key View 1	
Figure 4.1.3: Key View 2	
Figure 4.1.4: Key View 3	
Figure 4.1.5: Key View 4	
Figure 4.1.6: Key View 5	
Figure 4.1.7: Key View 6	
Figure 4.1.8: Key View 7	
Figure 4.1.9: Key View 8	
Figure 4.1.10: Key View 9	
Figure 4.1.11: Key View 10	
Figure 4.1.12: Key View 11	
Figure 4.1.13: Key View 12	
Figure 4.4.1: Aerial Comparison of Marine Stadium	
Figure 4.4.2: Layout of the 1932 Olympic Rowing Course	
Figure 4.8.1: Land Uses in the Project Vicinity	
Figure 4.8.2: Coastal Zone	
Figure 4.8.3: Zoning Designations in the Project Vicinity	
Figure 4.10.1: Public Service Facility Locations	
Figure 4.10.2: Water and Sewer Lines in the Project Vicinity	4.10-20
Figure 4.12.1: Construction Haul Routes	4.12-13

TABLES

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level	
of Significance	1-6
Table 3.A: Boater Terminology Definitions	3-3
Table 3.B: Slip Count and Size per Basin	
Table 3.C: Proposed Construction Phasing	3-11
Table 3.D: Discretionary Permits and Approvals	3-12
Table 4.2.A: Ambient Air Quality Standards	4.2-2
Table 4.2.B: Health Effects Summary of Some of the Common Pollutants Found	
in Air	4.2-5
Table 4.2.C: Attainment Status of Criteria Pollutants in the South Coast Air Basin	4.2-13
Table 4.2.D: Ambient Air Quality at the Long Beach Air Monitoring Stations	4.2-17
Table 4.2.E: Peak-Day Construction Emissions by Phase (lbs/day)	4.2-35
Table 4.2.F: Summary of Construction Emissions, Localized Significance by	
Phase	4.2-36
Table 4.5.A: Nearby Active Faults	4.5-3
Table 4.7.A: Water Quality Standards and Benchmarks	4.7-12
Table 4.7.B: Impaired Waters	4.7-17
Table 4.8.A: Consistency with Coastal Act Policies	4.8-14
Table 4.8.B: Consistency with SCAG Regional Policies	4.8-24
Table 4.9.A: Exterior Noise Limits, L _N (dBA)	4.9-5
Table 4.9.B: Maximum Interior Sound Levels, L _N (dBA)	4.9-5
Table 4.9.C: Typical Construction Equipment Noise Levels	4.9-10
Table 4.10.A: Fire Stations in Proximity to the Project Site	4.10-3
Table 4.10.B: Public Libraries in the Project Area	4.10-4
Table 4.10.C: City of Long Beach Solid Waste Disposal by Facility, 2005	4.10-6
Table 4.12.A: Alamitos Bay Marina Parking	4.12-3
Table 4.12.B: Construction Truck Trips by Phase	
Table 4.12.C: Project Trip Generation	4.12-7
Table 5.A: Alternatives Comparison Matrix	
Table 7.A: Mitigation and Monitoring Reporting Program	7-3

1.0 EXECUTIVE SUMMARY

1.1 INTRODUCTION

This Executive Summary has been prepared according to the California Environmental Quality Act (CEQA) Guidelines Section 15123 for the City of Long Beach (City) Environmental Impact Report (EIR) for the proposed Alamitos Bay Marina Rehabilitation Project. This EIR has been prepared by the City to analyze the proposed project's potential impacts on the environment, to discuss alternatives, and to propose mitigation measures for identified potentially significant impacts that will minimize, offset, or otherwise reduce or avoid those environmental impacts.

1.2 SUMMARY OF PROJECT DESCRIPTION

The Alamitos Bay Marina is located in the southeastern portion of Los Angeles County within the City. Alamitos Bay Marina was opened in the late 1950s and early 1960s; the Marina facilities are operated by the City of Long Beach. Although Alamitos Bay Marina is comprised of eight basins, the proposed project includes renovations only to Basins 1–7. Basin 8 is not included in the project, as addressed in this Draft EIR.

The proposed project would renovate the existing Marina facilities and enhance the existing recreational boating facilities within the harbor. The project encourages boating use by providing upgraded American with Disabilities (ADA) compliant facilities, upgraded restrooms, and dredged basins to ensure safe navigation. There are currently 1,967 existing slips in Basins 1 through 7. The proposed project includes installation of 1,646 slips in these basins, resulting in the loss of approximately 321slips. As of the date of this EIR, there are 1,430 customers in the Marina, so there would be a slip for every customer once the renovations are complete. However, should the number of correctly sized slips not be available at project completion, those customers would be placed in alternate slips until the appropriately sized slips become available.

Implementation of the project is anticipated to be accomplished in a 12-phase program, extending over approximately 6 years. The proposed project consists of a number of improvements to the existing Marina and includes the following: (1) dredging the Marina basins down to original design depths and/or original basin depths; (2) replacing and/or upgrading 13 restrooms along with their associated water and sewer laterals; (3) repairing the sea wall where necessary to reestablish the rock revetment along the slope to the basin floor; (4) completing dock and piling replacement; and (5) replacing the pavement in the Marina's parking lots. The project also includes the construction of an approximately 565-foot (ft) long dock located adjacent to Basin 4 at the southeast corner of the Long Beach Yacht Club

(LBYC). The long dock includes a 200 ft temporary section that would accommodate boaters during the renovations and would be removed upon project completion. Based on preliminary analysis, dredging activities would require mitigation for potential impacts to marine eelgrass. Therefore, the City has identified a site adjacent to the northeast shore of Marine Stadium to convert to an open space/habitat mitigation site The project includes two construction staging areas: one located in a parking lot on Marina Drive near Basin 2 and one located in a parking lot on Marina Drive near Basin 3, adjacent to the Marina Shipyard. Each of these project components is described in greater detail in Chapter 3.0, Project Description.

1.3 ALTERNATIVES

The following three alternatives to the proposed project were selected for consideration, including the No Project Alternative and alternative sites as required by CEQA:

- Alternative 1: No Project/No Development
- Alternative 2: Reduced Project Alternative
- Alternative 3: On-Site Dry Stack Storage Alternative

In evaluating an appropriate range of alternatives to the proposed project, a number of alternatives were considered and rejected by the Lead Agency. These included an alternative location, alternative habitat mitigation sites (Alamitos Bay Peninsula between Balboa and 56th Place, Cerritos Channel and Wetlands, Basin 6 North – Cerritos Channel, Downtown Marina/Long Beach Shoreline between Junipero Ave to 1st Street, Rainbow Marina along the south jetty/breakwater, and the Huntington Beach Wetlands Restoration Project) and an existing layout alternative. Each of these alternatives was rejected for differing reasons, as described further in Chapter 5.0, Alternatives.

The No Project/No Development Alternative would be environmentally superior to the proposed project on the basis of the physical impacts that would occur with this alternative. If there were no changes to the existing conditions on site, there would be no increase in construction traffic, construction noise, or construction and cumulative air emissions. However, the No Project Alternative would not provide Americans with Disabilities Act (ADA)-compliant facilities or provide upgraded and new dock facilities to safely serve the boating community and extend the useful life of the Marina.

The CEQA Guidelines require that if the environmentally superior alternative is the No Project Alternative, "the EIR also identify an environmentally superior alternative among the other alternatives" (CEQA Guidelines Section 15126.6(e)(2)). The Environmentally Superior Alternative, in terms of direct physical effects on the environment, is the Reduced Project Alternative.

The Reduced Project Alternative would eliminate construction activities associated with the proposed project's landside improvements (rehabilitation of the restroom facilities, parking lot repaving, and ADA access improvements), as well as eliminating construction of the long dock and reducing the dock area and number of slips in Basin 4. Therefore, direct physical effects on the environment as a result of construction would be reduced as compared to the proposed project.

Although this alternative would reduce the duration of project emissions, it would still result in the same significant construction-related and cumulative air quality emission impacts associated with the proposed project. Also, due to the existing location of sensitive receptors and type of construction, this alternative would still result in significant and unavoidable construction noise impacts. The Reduced Project Alternative would result in reduced construction impacts for cultural resources, geology and soils, hazardous materials, hydrology/water quality, and traffic compared to the proposed project because the improvements to landside facilities would not occur with this alternative. However, impacts related to these topics would still be less than significant, which is the same as what would occur with implementation of the proposed project.

For operational considerations, Alternative 2 would not increase energy efficiency or reduce potable water demand, as would occur with the renovation of restrooms under the proposed project. In addition, ADA access to the restroom facilities for handicapped and disadvantaged residents would not be provided, and no beneficial improvements to storm drain facilities would be implemented.

The Reduced Project Alternative meets some of the project objectives, but not to the same extent as the proposed project. The aging and deteriorating docks and slip facilities would be replaced, and recreational boating would be enhanced. However, because this alternative would result in a greater loss of smaller slips than the proposed project, it would potentially reduce the overall recreational opportunities for small boat owners and users when compared to the proposed project. Further, the goals of the Alamitos Bay Master Plan to remodel the restrooms and bring them up to current standards, and the objectives contained in the City's Open Space and Recreation Element related to modernizing the Marina condition, infrastructure, and amenities would not be fully implemented with the Reduced Project Alternative. The restroom facilities and parking areas would continue to deteriorate, and the costs associated with continued maintenance would continue to rise.

The alternatives analysis is described in greater detail in Chapter 5.0, Alternatives.

1.4 AREAS OF CONTROVERSY

Pursuant to State CEQA Guidelines Section 15123, this EIR acknowledges the areas of controversy and issues to be resolved that are known to the City of Long Beach or were raised during the scoping process.

In accordance with State CEQA Guidelines Section 15082, the City circulated a Notice of Preparation (NOP) on May 11, 2009, to agencies and interested individuals for a period of 30 days, during which time written comments were solicited pertaining to environmental issues/topics that the Draft EIR should evaluate. The major issues identified by the agencies included the following:

- Impacts related to identification and handling of potentially hazardous materials (refer to Section 4.6, Hazards and Hazardous Materials)
- Impacts to air quality (refer to Section 4.2, Air Quality)
- Impacts related to increased traffic and circulation conditions (refer to Section 4.12, Traffic and Circulation)
- Impacts related to regional planning and transportation policies (refer to Sections 4.8, Land Use, and 4.12, Traffic and Circulation)
- Impacts to marine biological resources (refer to Section 4.3, Biological Resources)
- Consistency with the provisions of the State Tidelands Grant (refer to Section 4.8, Land Use)

The City held a public scoping meeting on May 28, 2009, to present the proposed project and to solicit input from interested individuals regarding environmental issues that should be addressed in this Draft EIR. Major issues and concerns raised at the scoping meeting included: (1) project impacts to recreation within Marine Stadium and within the Marina (particularly to rowers); (2) project impacts to Marine Stadium, a historic resource; (3) safety concerns related to the narrowing of the Marina Channel between Basins 3 and 4; (4) public access to and availability of guest docks and other facilities during construction; (5) project impacts to water quality (e.g., silt and hazardous materials); (6) project-related noise impacts; (7) project impacts to views and aesthetics; (8) impacts to and/or loss of habitat; (9) consideration of alternatives; and (10) traffic-related project impacts.

The Draft EIR addresses each of these areas of concern or controversy in detail, examines project-related and cumulative environmental impacts, identifies significant adverse environmental impacts, and proposes mitigation measures designed to reduce or eliminate potentially significant impacts.

1.5 SUMMARY OF IMPACTS AND MITIGATION MEASURES

Table 1.A identifies the project environmental impacts, a significance determination, proposed mitigation measures, and level of significance after mitigation is incorporated into the project. Table 1.A also identifies cumulative impacts resulting from the proposed project in conjunction with the approved and pending cumulative projects. Environmental topics addressed in this EIR include: Aesthetics, Air Quality, Biological Resources, Cultural

DRAFT ENVIRONMENTAL IMPACT REPORT ALAMITOS BAY MARINA REHABILITATION PROJECT CITY OF LONG BEACH

Resources, Geology and Soils, Hazards and Hazardous Materials, Hydrology and Water Quality, Land Use, Noise, Public Services and Utilities, Recreation, and Traffic and Circulation.

Refer to Section 2.4 of this EIR for a discussion of additional effects found not to be significant through the Initial Study/Notice of Preparation process.

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
	AES	STHETICS	
Substantial adverse effect on a viewshed from a public viewing area (such as a park, scenic highway, scenic roadway, or other scenic vista)	Implementation of the proposed project will not disrupt existing scenic vistas or viewsheds visible on or from the project site.	No mitigation is required.	Less Than Significant
Substantial damage to scenic resources, including, but not limited to, trees, rock outcroppings, and historic buildings within a state scenic highway	Portions of Pacific Coast Highway (PCH) are designated as an Eligible State Scenic Highway. The closest historical resource to the project site is Marine Stadium, which is located to the north of the Marina, outside of the project boundaries, and not within view of the portion of PCH designated as an Eligible State Scenic Highway. Impacts are considered less than significant. The project will not impact any other scenic resources such as trees or rock outcroppings.	No mitigation is required.	Less Than Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
Substantial degradation of	The visual character of the	No mitigation is required.	Less Than
the existing visual character	Marina Basins would not		Significant
or quality of the site and its	change. The views of the newly		
surroundings	renovated restroom facilities		
	would be considered visual		
	improvements from the existing		
	condition.		
	Views of the long dock after		
	project completion would be		
	visible. The seawall on Naples		
	Island would be partially		
	obstructed, and depending on the		
	size of boats docked at the long		
	dock, views of Long Beach		
	Yacht Club (LBYC) may be		
	partially obstructed. Views of		
	the open marine waters or sky		
	would not be blocked, and these		
	changes would not impact the		
	visual character of this area of		
	Alamitos Bay.		

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
Creation of a new source of substantial light or glare,	The replacement of lighting associated with the proposed	No mitigation is required.	Less Than Significant
which would adversely	project would not create a		Significant
affect day or nighttime views	substantial new source of light		
in the area	or glare affecting day or		
	nighttime views in the area or		
	illuminate areas outside the		
	project boundary. The		
	replacement lighting would not increase the intensity of light to		
	sensitive viewers such as		
	residents in the surrounding area		
	due to the distance and		
	intervening uses between		
	residences and the Marina.		
	Lighting associated with		
	recreational boats is generally		
	low-level safety lighting and is		
	not expected to significantly		
	increase with project		
	implementation. Therefore, visual impacts relating to light or		
	glare would be considered less		
	than significant.		

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
Contribute to cumulative impacts	The proposed project would not contribute to potential	No mitigation is required.	Less Than Significant
in partic	cumulative impacts related to aesthetics or visual resources.		
	AIR	QUALITY	
Conflict with or obstruct implementation of the applicable air quality plan	The proposed project would not result in any population growth and is consistent with the City's General Plan designation for the site. In addition, the proposed project is not expected to result in any increase in long-term regional air quality emissions. Therefore, the project will not conflict with the Air Quality Management Plan (AQMP).	No mitigation required.	Less Than Significant
Violate any air quality standard or contribute substantially to an existing or projected air quality violation	The project would result in an exceedance of the South Coast Air Quality Management District (SCAQMD) daily threshold for nitrogen oxide (NO _X) during construction. Implementation of Mitigation Measure 4.2-1 would reduce the	4.2-1 Prior to commencement of construction the Marine Bureau Manager shall ensure that the final project plans and the construction contract include, but are not limited to, the following energy conservation and emission reduction measures:	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
	vehicle exhaust emissions during construction. However, the impact would remain significant and unavoidable for the duration of construction activities in Phases 2 and 3.	Fugitive Dust Controls. The project construction contractor shall develop and implement dust-control methods that shall achieve this control level in a South Coast Air Quality Management District (SCAQMD) Rule 403 dust control plan, designate personnel to monitor the dust control program, and order increased watering, as necessary, to ensure a 90 percent control level. Their duties shall include holiday and weekend periods when work may not be in progress. Additional control measures to reduce fugitive dust shall include, but are not limited to, the following: • Provide temporary wind fencing around sites	
		 being graded or cleared Cover truck loads that haul dirt, sand, or gravel or maintain at least 2 feet (ft) of freeboard in accordance with Section 23114 of the California Vehicle Code (CVC) Install wheel washers where vehicles enter and 	
		 exit unpaved roads onto paved roads, or wash off tires of vehicles and any equipment leaving the construction site Suspend all soil disturbance activities when winds exceed 25 miles per hour (mph) as 	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
		instantaneous gusts or when visible dust plumes emanate from the site and stabilize all disturbed areas	
		 Appoint a construction relations office to act as a community liaison concerning on-site construction activity, including resolution of issues related to particulate matter less than 10 microns in diameter (PM₁₀) generation 	
		Sweep all streets at least once a day using SCAQMD Rule 1186, 1186.1 certified street sweepers or roadway washing trucks if visible soil materials are carried to adjacent streets (recommend water sweepers with reclaimed water)	
		Apply water three times daily, or nontoxic soil stabilizers according to manufacturers' specifications, to all unpaved parking or staging areas or unpaved road surfaces or as needed to areas where soil is disturbed	
		Emission Controls for Nonroad Construction Equipment. Construction equipment shall meet the	
		United States Environmental Protection Agency	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
		(EPA) Tier 4 nonroad engine standards, where feasible. The Tier 4 standards become available starting in 2012.	
		Best Management Practices (BMPs) for Construction Equipment. The construction contractor shall implement the following BMPs on construction equipment, where feasible, to further reduce emissions from these sources.	
		 Use of diesel oxidation catalysts and/or catalyzed diesel particulate traps, as feasible Maintain equipment according to manufacturer 	
		 Maintain equipment according to manufacturer specifications Restrict idling of equipment and trucks to a maximum of 5 minutes (per California Air Resources Board [ARB] regulation) 	
		Use of high-pressure fuel injectors on diesel- powered equipment	
		Use of electricity from power poles rather than temporary diesel- or gasoline-powered generators	
		Construction Traffic Emission Reductions. The	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
		construction contractor shall implement the following measures to further reduce emissions from construction.	
		• Trucks used for construction (a) prior to 2015 shall use engines certified to no less than 2007 nitrogen oxide (NO _x) emissions standards and (b) in 2015 and beyond shall meet EPA 2010 emission standards.	
		Provide temporary traffic control such as a flag person during all phases of construction to maintain smooth traffic flow	
		Schedule construction activities that affect traffic flow on arterial systems to off-peak hours where possible	
		Reroute construction trucks away from congested streets or sensitive receptor areas	
		Provide dedicated turn lanes for movement of construction trucks and equipment on and off site	
		Configure construction parking to minimize traffic interference	
		Improve traffic flow by signal synchronization	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Impact	Mitigation Measures ¹	Significance After Mitigation
	All vehicles and equipment will be properly tuned and maintained according to manufacturer specifications.	
	 Reduce traffic speeds on all unpaved roads to 15 mph or less 	
	Emission Controls for Construction Tugboats. All tugboats used in construction shall meet the EPA Tier 2 marina engine standards, and if feasible, use construction tugs that meet the EPA Tier 3 marine engine standards. The Tier 3 standards become available starting in 2009.	
	Construction Tugboat Home Fleeting. The construction contractor shall require all construction tugboats that home fleet in the San Pedro Bay Port (SPBP) to (a) shut down their main engines, and (b) refrain from using auxiliary engines at dock or to use electrical shore power, if need be.	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
Result in a cumulative considerable net increase of any criteria pollutant for which the project region is non-attainment under an applicable federal or state ambient air quality standard (including releasing emissions which exceed quantitative thresholds for ozone precursors)	Building design and building operation for the proposed restroom facilities could contribute to increased amounts of carbon dioxide (CO ₂) and other greenhouse gases (GHGs) from use of electricity, natural gas, and other fuels.	 4.2-2 Prior to issuance of building permits, the Marine Bureau Manager shall ensure that the final construction drawings include the following building design energy conservation measures: Green Building Design for Restroom Buildings: Incorporate measures from the Leadership in Energy and Environmental Design (LEED) certification program and other green building guidelines that reduce greenhouse gas (GHG) emissions through either development density/design and/or energy conservation. The LEED for Retail—New Construction and LEED for Commercial Interiors programs developed by the United States Green Building Council are good sources for identifying measures and examples of energy conservation measures, including the following: Meet or exceed Title 24 requirements Incorporate ENERGY STAR-rated windows Incorporate ENERGY STAR-rated space heating and cooling equipment Incorporate hot water systems that are energy 	Less Than Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
		 efficient Incorporate ENERGY STAR-rated light fixtures 	
		 Incorporate ENERGY STAR-rated appliances Install/operate renewable electric generation systems, as appropriate and economically feasible 	
		4.2-3 Prior to issuance of building permits, the Marine Bureau Manager shall ensure that the final construction drawings of the building operations and maintenance plan include, but are not limited to, the following energy conservation measures:	
		• Compact Fluorescent Light Bulbs: All interior building lighting shall use compact fluorescent light bulbs. Fluorescent light bulbs produce less waste heat and use substantially less electricity than incandescent light bulbs.	
		• Energy Audits: Conduct a third-	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
		party energy audit every 5 years and install innovative power-saving technology where feasible, such as power factor correction systems and lighting power regulators. Such systems help to maximize usable electric current and eliminate wasted electricity, thereby lowering overall electricity use.	
	The project would not result in increases in long-term operational emissions because the capacity of the Marina would not be increased with the proposed project, and operations are not anticipated to change significantly. Therefore, the project would not contribute cumulatively to long-term local and regional air quality degradation.	No mitigation is required.	Less Than Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact		Mitigation Measures ¹	Level of Significance After Mitigation
	The project will not result in a new, ongoing source of GHG emissions; therefore, the project's contribution to cumulative GHG emissions and global climate change GCC is less than significant.	No mitig	ration is required.	Less Than Significant
Expose sensitive receptors to substantial pollutant concentrations	Calculated emissions rates for the proposed construction activities would not exceed the localized significance thresholds for the nearest sensitive receptors, under the condition that no more than 1 acre (ac) of parking lot repaving occurs at any one time.	4.2-4	Prior to issuance of building permits, the Marine Bureau Manager shall ensure that the final construction drawings and the construction contract indicate that no more than 1 acre (43,560 square feet) of parking lot pavement area shall be under construction for replacement at any one time during each phase of the project.	Less Than Significant
	Construction activities are expected to generate a temporary increase in carbon dioxide (CO ₂) emissions for the duration of such activities.	4.2-5	During all phases of demolition, dredging, and construction, the Marine Bureau Manager shall ensure that the contract to construct complies with the following rules for construction and operation to minimize the air quality impacts from the proposed project. The following measures are required and will reduce or minimize air pollutants	Less Than Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

	Potential Environmental		Level of Significance
Threshold of Significance	Impact	Mitigation Measures ¹	After Mitigation
- Control of the cont		generated by construction vehicles and equipment and fugitive dust emissions associated with earthmoving or excavation operations, or other soil disturbances, as identified in South Coast Air Quality Management District (SCAQMD) Rules 402 and 403. The following measures shall be printed on all final plans and drawings associated with the project:	
		During earthmoving or excavation operations, fugitive dust emissions shall be controlled by regular watering or other dust-preventive measures using the following procedures:	
		All material excavated shall be sufficiently watered to prevent excessive amounts of dust. Watering, with complete coverage, shall occur at least twice daily, preferably in the late morning and after work is done for the day.	
		All earthmoving or excavation activities shall cease during periods of high winds (i.e., winds greater than 20 miles per hour [mph] averaged	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

TIV 1 11 0 Ct 10t	Potential Environmental	3500 00 350 1	Level of Significance
Threshold of Significance	Impact	Mitigation Measures ¹	After Mitigation
		 over 1 hour). All material transported off site shall be either sufficiently watered or securely covered to prevent excessive amounts of dust. 	
		The area disturbed by earthmoving or excavation operations shall be minimized at all times.	
		After earthmoving or excavation operations, fugitive dust emissions shall be controlled using the following measures:	
		• Portions of the construction area to remain inactive longer than a period of 3 months shall be revegetated and watered until cover is grown.	
		All active portions of the construction site shall be watered to prevent excessive amounts of dust.	
		At all times, fugitive dust emissions shall be controlled using the following procedures:	
		On-site vehicle speed shall be limited to 15 mph.	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
		Road improvements shall be paved as soon as feasible, watered periodically, or chemically stabilized.	
		At all times during the construction phase, ozone precursor emissions from mobile equipment shall be controlled using the following procedures:	
		• Equipment engines shall be maintained in good condition and in proper tune according to manufacturer's specifications.	
		• On-site mobile equipment shall not be left idling for a period longer than 60 seconds.	
		Outdoor storage piles of construction materials shall be kept covered, watered, or otherwise chemically stabilized with a chemical wetting agent to minimize fugitive dust emissions and wind erosion.	
Create objectionable odors affecting a substantial number of people	Some objectionable odors may emanate from operation of diesel-powered construction equipment during construction of the project. These odors, however, would be limited to the	No mitigation required.	Less Than Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact		Mitigation Measures ¹	Level of Significance After Mitigation
	site only during the construction period and therefore would not be considered a significant impact.			
	The dredged material from Basin 1 may generate unpleasant odors when exposed to air and may result in odor impacts at the adjacent and nearby sensitive land uses. Mitigation Measure 4.6-3 in Section 4.6, Hazards and Hazardous Materials, requires the application of a mixture of Simple Green and water to the excavated sediment as part of an overall Soil Management Plan. Simple Green accelerates the decomposition process and will have the overall result of shortening the duration of odor emissions.	4.6-3	Soil Management Plan: The Office of Environmental Health Hazard Assessment (OEHHA) shall review the dredge materials removal workplan and shall list any additional requirements. Implementation of the workplan shall be overseen by the OEHHA for compliance with local, State, and federal regulations. Any additional sampling or contaminant material removal shall be subject to these same regulations. As part of the soil management plan, all disposal material will be characterized prior to disposal at a State landfill site. All hazardous waste will be disposed of in a Class I landfill. All other soils or solid waste will be disposed of at an unclassified landfill. In addition, during construction activities of the potentially impacted soils on site, monitoring will be required by the South Coast Air	Less Than Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
		Quality Management District (SCAQMD).	
		After removal of the contaminated materials from Basin 1 and during the drying process of these sediments/soils, a mixture of Simple Green and water (10:1) shall be lightly applied to the excavated sediments/soils. Simple Green accelerates the decomposition process and will have the overall result of shortening the duration of odor emissions.	
Contribute to cumulative impacts	The proposed project's construction activities would contribute cumulatively to the local and regional air pollutants, together with other projects under construction, and would result in temporary significant cumulative air quality impacts during construction activities associated with Phases 2 and 3. Mitigation Measure 4.2-1 would reduce construction emissions, but the impact would remain significant and adverse for the	See Mitigation Measure 4.2-1, Air Quality.	Significant and Unavoidable

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

	Potential Environmental			Level of Significance
Threshold of Significance	Impact		Mitigation Measures ¹	After Mitigation
	duration of construction.			
	BIOLOGIC	CAL RES	OURCES	
Substantial adverse effect,	Although there are no nesting	4.3-1	Prior to the start of any construction or	Less Than
either directly or through	sites in the vicinity of project		dredging activities, the Marine Bureau	Significant
habitat modifications, on any	construction, and construction		Manager shall verify that a qualified	
species identified as a	phasing will disturb only small		biologist has been retained and shall be	
candidate, sensitive, or	areas of the Marina at any one		on site to assess the roosting (and	
special-interest species in	time, construction activities may		foraging) behavior of waterbirds at the	
local or regional plans,	disturb the California brown		Marina immediately prior to any major	
policies, or regulations, or by	pelican (Pelecanus occidentalis)		construction disturbance. In the event of	
the CDFG or USFWS.	and the California least tern		an imminent threat to a special-status	
	(Sterna antillarum browni) if		species, the monitor shall immediately	
	present during such ac activities.		contact the Construction Manager. In	
			the event the Construction Manager is	
			not available, the monitor shall have the	
			authority to redirect or halt	
			construction activities if determined to	
			be necessary.	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact		Mitigation Measures ¹	Level of Significance After Mitigation
	Construction activities may disturb green sea turtles, if present during such activities.	4.3-2	Prior to the start of any construction or dredging activities, the Marine Bureau Manager shall verify that the following measures have been incorporated into the final project plans and construction contract in order to further reduce any potential impacts to green sea turtles: • A qualified marine biologist shall be on site during the construction period to monitor the presence of endangered species. The on-site biological monitor shall have the authority to halt construction operations and shall determine when construction operations can proceed. • Construction crews and work vessel crews shall be briefed on the potential for this species to be present and will be provided with identification characteristics of sea turtles, since they may occasionally be mistaken for seals or sea lions. • In the event that a sea turtle is	Less Than Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

TD1 1. 1.1. e.C	Potential Environmental	Mitigation Measures ¹	Level of Significance
Threshold of Significance	Impact	sighted within 100 meters of the construction zone, all construction activity shall be temporarily stopped until the sea turtle is safely outside the outer perimeter of construction. The onsite biological monitor shall have the authority to halt construction operation and shall determine when construction operations can proceed. • The biological monitor shall prepare an incident report of any green sea turtle activity in the project area and shall inform the construction manager to have his/crews be aware of the potential for additional sightings. The report shall be provided within 24 hours to the California Department of Fish and Game (CDFG) and the National Marine Fisheries Service (NMFS).	After Mitigation

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact		Mitigation Measures ¹	Level of Significance After Mitigation
	Dredging will remove	4.3-3	Prior to the start of any construction or	Less Than
	approximately 0.03 ac (1,373 sf)		dredging activities, the Marine Bureau	Significant
	of eelgrass vegetation in Basins		Manager shall ensure that an Eelgrass	
	2, 4, and 6.		Mitigation Plan has been included in the	
			contract for construction. The Plan shall	
			require that any direct losses to eelgrass	
			will be mitigated at a ratio of 1.2:1	
			according to the Southern California	
			Eelgrass Mitigation Policy (SCEMP) requirement. According to current	
			surveys, eelgrass to be impacted by the	
			project is 1,373 square feet (sf), which	
			would result in 1,648 sf to be mitigated	
			at the 1.2:1 mitigation ratio. As detailed	
			in the SCEMP, the actual amount of	
			eelgrass to be mitigated shall depend on	
			preconstruction surveys,	
			postconstruction surveys, and surveys at	
			a control site at the appropriate time	
			prior to the beginning of project	
			activities. The preferred mitigation area	
			is located adjacent to the northeast end	
			of Marine Stadium on a City of Long	
			Beach-owned storage site. A qualified	
			biologist shall monitor the successful	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact		Mitigation Measures ¹	Level of Significance After Mitigation
	No invasive Caulerpa taxifolia	4.3-7	establishment of the eelgrass mitigation site for a period of 5 years, in accordance with the Southern California Eelgrass Mitigation Policy. The Marine Bureau Manager shall	Less Than
	was present during surveys within the project site. However, if present, construction activities could contribute to the propagation of such species.	7.07	ensure that a field survey to investigate the presence of the invasive algae <i>Caulerpa taxifolia</i> is conducted 30 to 60 days prior to commencement of construction by qualified divers certified by the California Department of Fish and Game (CDFG) and National Marine Fisheries Service (NMFS) to conduct such surveys. The preconstruction <i>Caulerpa</i> surveys will be conducted ac according to the ac accepted criteria of the Southern California <i>Caulerpa</i> Action Team (SCCAT) for conducting surveys for the invasive algae and in ac accordance with the NMFS and CDFG <i>Caulerpa</i> survey protocols. In ac accordance with the recommendations of the Southern California Caulerpa Action Team (SCCAT), and according to the NMFS <i>Caulerpa</i> Control Protocol	Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

	Potential Environmental		Level of Significance
Threshold of Significance	Impact	Mitigation Measures ¹	After Mitigation
		(Version 3, adopted March 12, 2007	
		[NMFS 2007]), a survey must be	
		conducted in harbor areas that may be	
		disturbed. In areas that are expected to	
		be free of <i>Caulerpa</i> , a 20 percent visual	
		Surveillance Level survey is required	
		prior to any dredging. The survey will	
		also identify any other marine	
		vegetation in the proposed construction	
		area, including eelgrass. The Marine	
		Bureau Manager, or his/her designee,	
		will transmit the survey results via	
		Caulerpa Survey Reporting Form to	
		NMFS and the CDFG within 48 hours	
		of completion of the survey. If Caulerpa	
		is identified in the project area, the City,	
		NMFS, and CDFG will be notified	
		within 24 hours of completion of the	
		survey. In the event that Caulerpa is	
		detected, disturbance shall not be	
		conducted until such time as the	
		infestation has been isolated, treated, or	
		the risk of spread from the proposed	
		disturbing ac activity is eliminated in ac	
		accordance with Section F of the	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
		Caulerpa Control Protocol.7	
Substantial adverse effect on any riparian habitat or other sensitive natural community identified in local or regional plans, policies, regulations or by the CDFG or USFWS.	The land side portion of the project site is currently developed with parking lots and restroom facilities and is sparsely landscaped with nonnative landscape and ornamental vegetation. Longterm operations at the renovated Marina would result in conditions similar to the existing setting and would not have impacts on wildlife or habitat from ongoing Marina operations.	No mitigation is required.	Less Than Significant
Substantial adverse effect on federally protected wetlands as defined by Section 404 of the Clean Water Act (including, but not limited to, marsh, vernal pool, coastal, etc.) through direct removal, filling, hydrological interruption, or other means.	Dredging and pile replacement will generate temporary increases in turbidity, reductions in dissolved oxygen, and possible localized increases in the dissolved concentrations of sediment-bound contaminants. The City will implement the required dredging water quality monitoring plan as set forth by	See Mitigation Measures 4.7-5 and 4.7-6 as required in Section 4.7, Water Quality and Hydrology: No additional mitigation is required.	Less Than Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

	Potential Environmental			Level of Significance
Threshold of Significance	Impact		Mitigation Measures ¹	After Mitigation
	the Regional Water Quality			
	Control Board (RWQCB).			
	Mitigation Measures 4.7-5 and			
	4.7-6 (as outlined in Section 4.7,			
	Water Quality and Hydrology)			
	require that the appropriate			
	dredging permits are obtained			
	and that dredging Best			
	Management Practices (BMPs)			
	are incorporated into the project			
	to ensure that impacts related to			
	the effects of turbidity,			
	construction dredging, and			
	piling replacement are reduced			
	to a less than significant level.			
	No additional mitigation is			
	required.			
Interfere substantially with	The project includes relocation	4.3-6	Prior to issuance of any demolition or	Less Than
the movement of any native	of several trees to accommodate		construction permits, the Marine Bureau	Significant
resident or migratory fish or	the restroom renovations.		Manager shall ensure that the following	
wildlife species or with	Construction activities may		provisions are incorporated into the final	
established native resident or	cause the potential abandonment		project plans and construction contract	
migratory wildlife corridors,	of nests by migratory birds.		for the purpose of protecting nesting	
or impede the use of native	Construction activities		birds within the study area during	
wildlife nursery sites.	associated with the proposed		construction:	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
	project may result in some temporary disruptions to the roosting activities of the great blue heron.	• Tree and vegetation removal shall be restricted to outside the likely ac active nesting season (January 1– September 1) for those bird species present or potentially occurring within the project area. That time period is inclusive of most other birds' nesting periods, thus maximizing avoidance of impacts to any nesting birds. If construction must be completed during the breeding season listed above, surveys for nesting birds shall be conducted at least 15 days prior to construction. Should an occupied nest be detected, the City will consult with the California Department of Fish and Game (CDFG) to determine an appropriate means for reducing impacts to nesting birds prior to tree removal. If nesting birds are observed within the vicinity, a buffer from the nest shall be established. The size of the buffer	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
		is dependent on the species and shall be determined by a qualified biologist. The buffer shall be delineated by roping the boundaries of construction and shall remain in place until the nest is abandoned or the young have fledged.	
Conflict with any local policies or ordinances protecting biological resources, such as tree preservation policy or ordinance.	The City also requires that the project remove existing trees adjacent to the existing restroom structures in the parking lots. The project will comply with City of Long Beach Municipal Code (Ordinance C-7642) requiring that a permit be obtained from the Director of Public Works prior to any demolition or construction activities. As required, the trees would be identified, mapped, and measured prior to removal, and landscape ornamental trees would be replaced on a 1:1 basis, per the City's Tree Removal Ordinance. Therefore,	No mitigation is required.	Less Than Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
	impacts related to this issue are considered less than significant, and no mitigation is required.		
Conflict with the provisions of an adopted HCP, NCCP, or other approved local, regional, or state habitat conservation plan.	No conservation plans exist for the project site. Therefore, no impacts to the provisions of any adopted conservation plan are expected.	No mitigation is required.	Less Than Significant
Potential to degrade the environment, or substantially reduce the habitat of a fish or wildlife species, cause a fish or wildlife population to drop below self-sustaining levels, threaten to eliminate a plant or animal community, or reduce the number or restrict the range of a rare or endangered plant or animal.	Dredging and pile replacement could disturb sediments and cause turbidity effects, resulting in degradation of water quality that could affect several marine species, habitat, and fishes.	4.3-4 Prior to issuance of any demolition or construction permits, the Marine Burea Manager shall provide verification that the following provision has been included in the contract for project construction: that a qualified biologist has been retained to implement the following measures, which shall be incorporated during all phases of construction in order to minimize impacts on eelgrass and other biologica resources:	
		Impacts to eelgrass beds shall be avoided where practical and feasible A project marine biologist shall	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
		mark the positions of eelgrass beds with buoys prior to the initiation of any construction to minimize damage to eelgrass beds outside the construction zone. To assist the construction crew in avoiding unnecessary damage to eelgrass, the project marine biologist shall meet with the construction crews prior to dredging to review areas of eelgrass to avoid and to review proper construction techniques.	
		Barges and work vessels shall avoid impacts to eelgrass beds in Basins 2 and 4. Barges and work vessels shall be operated in a manner to ensure that eelgrass beds are not impacted through grounding, propeller damage, or other ac activities that may disturb the seafloor. Such measures shall include speed restrictions, establishment of off-limit areas, and use of shallow draft vessels.	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

TD1 1 11 6 C1 16	Potential Environmental		7. m. 1	Level of Significance
Threshold of Significance	Impact		Mitigation Measures ¹	After Mitigation
			A qualified marine biologist shall	
			monitor the construction process on	
			a weekly basis to ensure that all	
			water quality best management practices (BMPs) are implemented	
			and to assist the project engineer in	
			avoiding and minimizing	
			environmental effects to benthic	
			communities, including eelgrass.	
			Within 30 days after the project is	
			completed, a post-construction	
			marine biological survey shall be	
			conducted to determine the extent of	
			any construction impacts on eelgrass	
			habitat. The survey report will be	
			completed within 30 days and shall be submitted to the California	
			Coastal Commission and the United	
			States Army Corps of Engineers.	
			States Army Corps of Engineers.	
		4.3-5	Prior to issuance of any demolition or	
			construction permits, the Marine Bureau	
			Manager shall verify that the following	
			measures have been incorporated into	
			the final project plans and construction	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
		contract. The construction contractor shall be responsible for ensuring that the following measures are implemented during all phases of construction in order to minimize impacts on biological resources:	
		• No construction materials, equipment, debris, or waste shall be place or stored where it may be subject to tidal erosion and dispersion. Construction materials shall not be stored in contact with the soil. Any construction debris within the temporary cofferdam area shall be removed from the site at the end of each construction day.	
		Reasonable and prudent measures shall be taken to prevent all discharge of fuel or oily waste from heavy machinery or construction equipment or power tools into Alamitos Bay. Such measures include deployed oil booms and a silt curtain around the proposed	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Cianificance	Potential Environmental	Mitigation Magazzas 1	Level of Significance
Threshold of Significance	Impact	construction zone at all times to minimize the spread of any ac accidental fuel spills, turbid construction-related water discharge, and debris. Other measures include training construction workers on emergency spill notification procedures, proper storage of fuels and lubricants, and provisions for on-site spill response kits. • All trash shall be disposed of in the proper trash receptacles at the end of each construction day. Any	After Mitigation
		 construction debris shall be removed from the site. During construction, floating booms shall be used to assist in containing debris discharged. Any debris discharged shall be removed as soon as possible but no later than the end of each day. If turbid conditions are generated during construction, including dredging or pile driving, a silt 	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
		curtain shall be utilized to control turbidity. The City of Long Beach shall limit, to the greatest extent possible, the suspension of benthic sediments into the water column.	
		The City shall implement all the requirements of the Department of the Army Permit and the RWQCB WQC, This includes the anticipated dredging water quality monitoring plan set forth by the RWQCB.	
		 Construction methods shall be used that are the least damaging to benthic sediments and organisms. 	
		Reasonable and prudent measures shall be taken to prevent all discharge of fuel or oily waste from heavy machinery or construction equipment or power tools into Alamitos Bay. The City of Long Beach shall have adequate equipment available to contain such spills immediately.	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

			Level of
	Potential Environmental	3.50.0 .0 3.5	Significance
Threshold of Significance	Impact	Mitigation Measures ¹	After Mitigation
Contribute to cumulative	The proposed project would not	No mitigation is required.	Less Than
impacts	contribute to potential		Significant
	cumulative impacts related to		
	biological resources.		
		HISTORIC RESOURCES	T
Cause a substantial adverse	Marine Stadium is listed on the	No mitigation is required.	Less Than
change in the significance of	California Register of Historical		Significant
a historic resource as	Resources (California Register),		
defined in Section 15064.5	the California Historical		
	Landmarks (CHL; No. 1014),		
	and the California Points of		
	Historical Interests (PHI; No.		
	19-186115). The proposed		
	project, including the proposed		
	open water habitat mitigation		
	site, would not detract from the		
	integrity of any historical,		
	structural, or operational		
	elements of Marine Stadium that		
	contribute to its being a historic		
	resource. Therefore, no		
	substantial adverse change in the		
	significance of a historic		
	resource as defined in Section		
	15064.5 would occur.		

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
Cause a substantial adverse	There are no recorded	No mitigation is required.	Less Than
change in the significance of	archaeological resources located		Significant
an archaeological resource	within the project boundaries.		
pursuant to Section 15064.5	The proposed improvements		
	would be located in areas that		
	were previously disturbed or		
	dredged. Therefore,		
	implementation of the proposed		
	project would not disturb		
	sensitive archaeological soils,		
	and an adverse change in the		
	significance of an archaeological		
	resource pursuant to Section		
	15064.5 would not occur.		
Directly or indirectly	There are no recorded	No mitigation is required.	Less Than
destroy a unique	paleontological resources		Significant
paleontological resource or	located within the project		
site or unique geologic	boundaries. The proposed		
feature	improvements would be located		
	in areas that were previously		
	disturbed or dredged. Therefore,		
	implementation of the proposed		
	project would not disturb		
	sensitive paleontological soils,		
	and impacts are considered less		

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
	than significant.	<u> </u>	
Disturb any human remains, including those found outside of formal cemeteries	Human remains are unlikely to be located in the project area due to previous disturbance of project area soils and waters. However, in the unlikely event that human remains are encountered during construction activities, adherence to existing standard construction regulations, including State Health and Safety Code Section 7050.5, would reduce potential adverse impacts to human remains to less than significant levels, and no further mitigation	No mitigation is required.	Less Than Significant
Contribute to cumulative	is necessary. The proposed project would not	No mitigation is required.	Less Than
impacts	contribute to potential cumulative impacts related to cultural resources.	Two minigution is required.	Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

	Potential Environmental		Level of Significance
Threshold of Significance	Impact	Mitigation Measures ¹	After Mitigation
		GY AND SOILS	
Expose people or structures to potential substantial adverse effects, including the risk of loss, injury, or death, involving rupture of a known earthquake fault, as delineated on the most recent Alquist-Priolo Earthquake Fault Zoning Map issued by the State Geologist for the area or based on other substantial evidence of a known fault, strong seismic ground shaking, and seismic-related ground failure, including liquefaction or landslides.	The project site is not located within a currently designated Alquist-Priolo Earthquake Fault Zone and is not expected to experience primary surface fault rupture or related ground deformation. However, significant ground shaking or secondary seismic ground deformation effects could occur at the site should a major seismic event occur along the Newport-Inglewood Structural Zone.	4.5-1 Prior to issuance of building permits, the Marine Bureau Manager shall verify that recommendations contained in the Geotechnical Evaluation prepared for the proposed project (Ninyo and Moore, February 2007) have been incorporated into final construction drawings. Design and grading construction shall be performed in accordance with the most current California Building Code in use by the City of Long Beach, the most current local grading regulations, and recommendations of the project geotechnical consultant.	Less Than Significant
Substantial soil erosion or the loss of topsoil.	There is the potential for soil erosion to occur at the site during project implementation. Construction of the proposed project includes excavation of land side soils to develop the open space/habitat mitigation	See Mitigation Measure 4.2-5 (Section 4.2, Air Quality). See Mitigation Measures 4.7-2 and 4.7-3 (Section 4.7, Hydrology and Water Quality). No further mitigation is required.	Less Than Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
	site, minor grading of land side		
	soils associated with repaving of		
	parking areas, trenching for		
	utilities, and reconstruction of		
	the restrooms.		
	Mitigation measures are required		
	to reduce fugitive dust and		
	transport of soil (refer to Section		
	4.2, Air Quality, and Section		
	4.7, Hydrology and Water		
	Quality, respectively). With		
	implementation of these		
	standard control measures, soil		
	erosion potential will be reduced		
	to less than significant levels.		
	No additional mitigation is		
	required.		
Be located on a geologic	There are no geologic units or	See Mitigation Measure 4.5-1 above.	Less Than
unit or soil that is unstable,	soils that would become		Significant
or that would become	unstable as a result of the		
unstable as a result of the	proposed project; however,		
project, and potentially	seismically induced lateral		
result in on-site or off-site	spread could occur during an		
landslide, lateral spreading,	earthquake event.		

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
subsidence, liquefaction, or			
collapse.	Due to the variability of the on- site soils, the potential for liquefaction would vary across the site. Seismically induced liquefaction could result in damage to structures.		
	The project site is not located near any known historical landslides, and the site topography is relatively level. No impacts related to landslides are anticipated.		
Be located on expansive soil, as defined in Table 18-1-B of the Uniform Building Code, creating substantial risks to life or property.	The soils underlying the project site include sand, clay, and silt. The clay material is considered expansive. However, due to the relatively high groundwater levels, the soils are anticipated to remain relatively wet, which would reduce the potential effects of the expansive soils on site.	See Mitigation Measure 4.5-1 above.	Less Than Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
Be incapable of adequately	The proposed project would	No mitigation is required.	Less Than
supporting the use of septic	utilize the existing sewer system		Significant
tanks or alternative	and does not include the use of		
wastewater disposal systems	septic tanks or alternative		
where sewers are not	methods for disposal of		
available for the disposal of	wastewater. Therefore, no		
wastewater.	impacts related to this issue		
	would occur.		
Contribute to cumulative	The proposed project would not	No mitigation is required.	Less Than
impacts	contribute to potential		Significant
	incremental or cumulative		
	impacts related to geology and		
	soils.		
		AZARDOUS MATERIALS	
Create a significant hazard to	Dredging within Basins 2–7 has	4.6-1 Prior to Prior to issuance of any permits	Less Than
the public or the	been determined to be	allowing dredging in Basin 1, the City	Significant
environment through the	nonhazardous, and it is unlikely	of Long Beach (City) shall conduct	
routine transport, use, or	that any dredging activities in	additional laboratory testing of the	
disposal of hazardous	those basins will pose a concern	sediment materials from Basin 1.	
materials	through the routine transport,	Additional testing shall be conducted	
	use, or disposal of sediment	prior to disposal of the contaminated	
	material. However, a portion of	soils to determine if concentrations of	
	sediments in Basin 1 have tested	mercury exceed the Soluble Threshold	
	for mercury levels that exceeded	Limit Concentration (STLC) for	
	acceptable thresholds for ocean	mercury at 0.2 milligrams per liter	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact		Mitigation Measures ¹	Level of Significance After Mitigation
	disposal, and would be tested and disposed of at an appropriate State-certified landfill. Transport of these contaminated materials could potentially pose a hazard to the public or environment.		(mg/L) and are considered hazardous by State standards (California Code of Regulations [CCR], Title 22, Section 66261.1–66261.126), and/or are considered hazardous by federal standards (Resource Conservation Recovery Act [RCRA]), where mercury concentrations exceed the federal threshold of 0.2 mg/L, as determined from toxicity characteristic leaching procedure (TCLP) extract testing (TCLP method shall be determined by leaching potential).	
		4.6-2	Prior to issuance of any permits allowing dredging in Basin Basin 1, the City of Long Beach shall conduct a Human Health Risk evaluation to determine the level of exposure to potentially hazardous levels of mercury during construction activities.	
		4.6-3	Soil Management Plan: The Office of Environmental Health Hazard Assessment (OEHHA) shall review the	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

	Potential Environmental		Level of Significance
Threshold of Significance	Impact	Mitigation Measures ¹	After Mitigation
		dredge materials removal workplan and	
		shall list any additional requirements.	
		Implementation of the workplan shall be	
		overseen by the OEHHA for compliance	
		with local, State, and federal	
		regulations. Any additional sampling or	
		contaminant material removal shall be	
		subject to these same regulations. As	
		part of the soil management plan, all	
		disposal material will be characterized	
		prior to disposal at a State landfill site. All hazardous waste will be disposed of	
		in a Class I landfill. All other soils or	
		solid waste will be disposed of at an	
		unclassified landfill. In addition, during	
		construction activities of the potentially	
		impacted soils on site, monitoring will	
		be required by the South Coast Air	
		Quality Management District	
		(SCAQMD).	
		After removal of the contaminated materials from	
		Basin 1 and during the drying process of these	
		sediments/soils, a mixture of Simple Green and	
		water (10:1) shall be lightly applied to the	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact		Mitigation Measures ¹	Level of Significance After Mitigation
			ed sediments/soils. Simple Green	
			tes the decomposition process and will overall result of shortening the duration of	
		odor em	_	
Create a significant hazard to	Construction activities could	4.6-4	During all excavation activities, the	Less Than
the public or the	result in the accidental spill or		Marine Bureau Manager shall ensure	Significant
environment through	exposure of hazardous materials		that all construction subcontractors	
reasonable foreseeable upset	to workers or the public.		comply with the appropriate health and	
and accident conditions			safety measures required by the	
involving the release of	Contaminated groundwater, if		Occupational Safety and Health	
hazardous materials into the	present on site, could be		Administration (OSHA). In the event	
environment	encountered during grading or excavation activities.		that groundwater is encountered during grading or excavation activities, all	
	excavation activities.		construction activities shall be	
	Due to the age of the existing		terminated in the immediate area until	
	restroom structures, there is a		the groundwater is investigated for	
	potential for exposure to		potentially hazardous content. In the	
	asbestos-containing materials		event that suspicious odors are observed	
	(ACMs) and/or lead-based		in soil, construction shall also be	
	paints (LBPs)		terminated until the soil is properly	
			characterized for hazardous waste	
	Proposed resurfacing of the		content. Appropriate measures shall be	
	parking lots may disturb or		taken in compliance with all applicable	
	remove existing transformer-		regulations for the characterization and	
	mounted utility poles. Impacted		disposal of hazardous materials.	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact		Mitigation Measures ¹	Level of Significance After Mitigation
	soil or groundwater from leaking transformers containing polychlorinated biphenyls (PCBs), if present on site, may pose a concern to worker safety.	4.6-5	Prior to the issuance of any demolition permits and at least 10 days prior to any demolition work for proposed improvements, the Marine Bureau Manager shall notify and submit fees to the South Coast Air Quality Management District (SCAQMD) in compliance with SCAQMD Rule 1403, Asbestos Emissions from Demolition/Renovation Activities. Contractors shall adhere to the requirements of SCAQMD Rule 1403 during all construction and demolition activities.	
		4.6-6	Prior to the issuance of any demolition permits, the Marine Bureau Manager shall provide evidence that a certified asbestos consultant has conducted an asbestos survey of the existing concrete materials. If asbestos-containing material (ACM) is found, it shall be removed and disposed of by a licensed and certified asbestos abatement	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact		Mitigation Measures ¹	Level of Significance After Mitigation
			contractor in accordance with requirements outlined by the local county health department.	
		4.6-7	Prior to the issuance of any demolition permits, the Marine Bureau Manager shall provide evidence that a certified lead-based paint (LBP) consultant has conducted LBP surveys in the areas where paint materials may be removed or disturbed on existing structures. If LBPs are found, they shall be removed and disposed of by a licensed and certified LBP contractor in accordance with requirements outlined by the local county health department.	
		4.6-8	Prior to the issuance of any demolition permits, the City of Long Beach shall conduct the inspection of utility polemounted transformers within the project area for leaks. Leaking transformers shall be considered a potential for polychlorinated biphenyl (PCB) hazard unless tested and shall be handled	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
		accordingly. If the removal of utility poles is anticipated, all treated wooden poles may have a potential for creosote. Areas immediately surrounding the utility pole shall be tested and handled accordingly.	
Emit hazardous emissions or handle hazardous or acutely hazardous materials, substances, or waste within 0.25 mi of an existing or proposed school	Basin 7 of the project site is located approximately 0.25 mile (mi) south of Naples Elementary School. The uses proposed are similar to existing land uses on site and are not expected to introduce significant amounts of hazardous materials or waste. Although unlikely, sensitive receptors at the school could be exposed to hazardous emissions, materials, or substances.	See Mitigation Measures 4.6-1 through 4.6-8.	Less Than Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
Be located within an airport land use plan, or where such	The project site is not located within an airport land use plan	No mitigation is required.	Less Than
a plan has not been adopted	area or within 2 mi of a public		Significant
within 2 mi of a public	airport.		
airport or public use airport,			
resulting in a safety hazard for people residing or			
working in the project area			
Be located within the	The project site is not located	No mitigation is required.	Less Than
vicinity of a private airstrip,	within the vicinity of a private		Significant
resulting in a safety hazard	airport.		
for people residing or working in the project area			
Impair implementation of or	The proposed project is a	No mitigation is required.	Less Than
physically interfere with an	continuation of existing land		Significant
adopted emergency response	uses and does not result in an		
plan or emergency	intensification of use or alter		
evacuation plan	access on or in the vicinity of the project site. Impacts to		
	emergency response or access		
	are considered less than		
	significant.		
Expose people or structures	The project site is not located	No mitigation is required.	Less Than
to a significant risk of loss,	adjacent to wildlands, and no		Significant
injury, or death involving	impacts related to wildland fires		

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact		Mitigation Measures ¹	Level of Significance After Mitigation
wildland fires, including where wildlands are adjacent to urbanized areas or where residents are intermixed with wildlands	are anticipated.		William Wedsures	Tittel Whighton
Contribute to cumulative impacts	Based on the distance to the nearest cumulative project and the amount of hazardous materials use associated with the proposed project, the project's contribution to cumulative hazards and hazardous materials impacts would be considered less than significant.		ntion is required.	Less Than Significant
Violate any water quality	HYDROLOGY A Impacts to water quality due to	4.7-1	Prior to issuance of a grading permit, the	Less Than
standards or waste discharge requirements, and/or otherwise substantially degrade water quality.	Marina operations and boater activities are expected to be less than significant because adherence to the Long Beach Marina Environmental Policies is required for boaters and Marina employees. In addition, the Marina provides four sewage	7./-1	Marine Bureau Manager shall verify that construction plans for the project include features meeting the applicable construction activity Best Management Practices (BMPs) and erosion and sediment control BMPs published in the California Storm Water BMP Handbook—Construction Activity or	Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

	Potential Environmental		Level of Significance
Threshold of Significance	Impact	Mitigation Measures ¹	After Mitigation
	pump-out stations. Because uses	equivalent. The construction contractor	
	on site would not change, and	shall be required to submit a Storm	
	because there would be fewer	Water Pollution Prevention Plan	
	boats in the Marina, operational	(SWPPP) to the City that includes the	
	impacts to water quality are	BMP types listed in the handbook or	
	expected to remain similar to	equivalent. The SWPPP shall be	
	existing conditions and are	prepared by a civil or environmental	
	considered less than significant.	engineer and will be reviewed and	
		approved by the City Building Official	
	Construction activities	prior to the issuance of any grading or	
	associated with the renovations	building permits. The SWPPP shall	
	to restrooms and parking lots	reduce the discharge of pollutants to the	
	have the potential to temporarily	maximum extent practicable using	
	impact water quality.	BMPs, control techniques and systems,	
		design and engineering methods, and	
	Construction activities	such other provisions as appropriate. A	
	associated with dredging	copy of the SWPPP shall be kept at the	
	activities have the potential to	project site.	
	temporarily impact water		
	quality.	The SWPPP shall meet the requirements	
		of the General Construction Permit and	
	Construction activities	shall identify potential pollutant sources	
	associated with the replacement	associated with construction activities;	
	of pilings and docks and repairs	identify non-storm water discharges;	
	to seawalls have the potential to	develop a water quality monitoring and	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact		Mitigation Measures ¹	Level of Significance After Mitigation
	temporarily impact water quality.		sampling plan; and identify, implement, and maintain BMPs to reduce or eliminate pollutants associated with the construction site. The BMPs identified in the SWPPP shall be implemented.	
			in the SWPPP shall be implemented during project construction. The SWPPP Notice of Termination (NOT) shall be submitted to the State Water Resources Control Board (SWRCB) upon completion of construction and	
		4.7-2	stabilization of the site. Prior to issuance of demolition and grading permits, the Marine Bureau	
			Manager shall demonstrate to the Director of Long Beach Development Services, or their designee, that compliance with the provisions of the	
			National Pollutant Discharge Elimination System (NPDES) General Permit for Storm Water Construction and Land Disturbance Activities, and	
			any subsequent permit as they relate to construction activities for the project has been obtained. This will include	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact		Mitigation Measures ¹	Level of Significance After Mitigation
		4.7-3	submission of the Permit Registration Documents, including a Notice of Intent (NOI), a risk assessment, site map, Storm Water Pollution Prevention Plan (SWPPP), annual fee, and signed certification statement to the State Water Resources Control Board (SWRCB) at least 14 days prior to the start of construction. Prior to issuance of demolition and	
		4., 5	grading permits, the Marine Bureau Manager shall provide evidence that a Standard Urban Storm Water Mitigation Plan (SUSMP) for the project has been prepared in accordance with the Los Angeles County SUSMP and the Municipal National Pollutant Discharge Elimination System (NPDES) Permit. The project SUSMP shall identify all of the Nonstructural and Structural Best Management Practices (BMPs) that will be implemented as part of the project in order to reduce impacts to water quality to the maximum extent practicable by	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact		Mitigation Measures ¹	Level of Significance After Mitigation
I m osnoru or signmeunee	Impue		addressing typical land use pollutants	TATULE IVALUE GROUND IN
			and pollutants that have impaired the	
			Alamitos Bay. The SUSMP shall be	
			reviewed and approved by the City of	
			Long Beach Building Official prior to	
			issuance of a grading permit.	
		4.7-4	Prior to the issuance of any construction	
			permits, the Marine Bureau Manager	
			shall provide verification in the record	
			that approval to initiate the City's	
			contract with AES (to increase pumping	
			rates) has been incorporated into project	
			plans and will be implemented in the	
			event that water quality standards are	
			exceeded during construction activities associated with Basins 6-North and	
			6-South (Basins 6-N and 6-S). The	
			construction contractor shall be	
			responsible for notifying the Marine	
			Bureau Manager in the event that	
			increased flushing in the Bay is needed,	
			should water quality remain impaired	
			(i.e., water quality standards are	
			exceeded) beyond 2 days after dredging	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
		in Basins 6-N or 6-S.	
		4.7-5 Prior to the issuance of any construction permits, the Marine Bureau Manager shall provide verification that authorization has been obtained from: (1) the United States Army Corps of Engineers (Corps) under the Section 404 Permit program for the discharge of fill material into jurisdictional waters; (2) the Corps, under Section 10 of the Rivers and Harbors Act for the disposal of dredged material and placement of piles and riprap; and (3) the Corps, under Section 103 of the Marine Protection Research and Sanctuaries Act for the transportation of dredged material for ocean disposal. In addition, standard conditions of the Corps permits require Section 401 water quality certification by the Regional Water Quality Control Board (RWQCB). In order to obtain these authorizations, the City shall develop a mitigation plan	
		subject to review and approval by the	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
	•	appropriate resource agencies (Corps, United States Fish and Wildlife Service [USFWS], National Marine Fisheries Service [NMFS], California Department of Fish and Game [CDFG], and RWQCB).	
		4.7-6 Prior to the issuance of any construction permits, the Marine Bureau Manager shall demonstrate in the record that Best Management Practices (BMPs) for all dredging activities, as listed in Appendix F of this document, have been incorporated into project plans in order to reduce impacts to water quality to the maximum extent practicable. The construction contractor shall be responsible for performing and documenting the application of BMPs identified in this document.	
		4.7-7 Prior to the issuance of any construction permits, the Marine Bureau Manager shall provide verification in the record that a trash and debris containment	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
		boom has been incorporated into project plans and will be implemented during all dock removal and replacement activities in order to reduce impacts to water quality to the maximum extent practicable. The construction contractor shall be responsible for performing and documenting the application of the trash and debris containment boom.	
Substantially deplete groundwater supplies or interfere substantially with groundwater recharge such that there would be a net deficit in aquifer volume or a lowering of the local groundwater level (e.g., the production rate of preexisting nearby wells would drop to a level that would not support existing land uses or planned uses for which permits have been granted).	The project site is not located within a groundwater recharge basin, and there would be no impact to groundwater supply with implementation of the proposed project. Historic high-water groundwater is estimated to be approximately 8 feet (ft) below the existing ground surface. This level is deeper than the proposed excavation for repaving the parking lots and renovating the restroom structures. Therefore, impacts to groundwater would	No mitigation is required.	Less Than Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
511 5 11 5 12 5	not be significant.		9.11
Substantially alter the existing drainage pattern of the site or area, including through the alteration of the course of a stream or river, in a manner which would result in substantial erosion or siltation on- or off-site, or substantially increase the rate or amount of surface runoff in a manner in which would result in flooding on- or off-site; and/or create or contribute runoff water that would exceed the capacity of existing or planned storm water drainage systems or provide substantial additional sources of polluted runoff.	The surface area of the parking lot is not being increased, and therefore no increase in storm water runoff is expected. In addition, the proposed project includes installation of storm drain inserts (filters) into the storm drains located in the parking lot. Storm water collection and treatment prior to discharge into the Marina will reduce contaminant levels and protect the existing water quality. As a result, the proposed project will result in improved drainage and storm water treatment over existing conditions.	No mitigation is required.	Less Than Significant
Place housing within a 100- year flood hazard area as mapped on a federal Flood Hazard Boundary or Flood	No housing is proposed as part of the proposed project.	No mitigation is required.	Less Than Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
Insurance Rate Map or other			
flood delineation map.			
Place within a 100-year	The proposed project replaces or	No mitigation is required.	Less Than
flood hazard area structures	renovates 13 restroom structures		Significant
that would impede or	within their existing parking		
redirect flood flows.	lots. No new structures are		
	proposed that would impede or		
	redirect flood flows.		
Expose people or structures	The proposed project is not	No mitigation is required.	Less Than
to a significant risk of loss,	within an inundation area for the		Significant
injury, or death involving	failure of a levee or dam.		
flooding as a result of the	Therefore, flooding as a result of		
failure of a levee or dam.	the failure of a levee or dam is		
	considered less than significant.		
Expose people or structures	The proposed project is located	No mitigation is required.	Less Than
to a significant risk of loss,	in a coastal bay and is within a		Significant
injury, or death involving	seiche and tsunami influence		
inundation by seiche,	area. The proposed project		
tsunami, or mudflow.	would not change or worsen this		
	existing condition and involves a		
	renovation of existing facilities.		
	Because the site is not located in		
	a hilly area, it is not considered		
	to be at a high risk for		
	inundation by mudflow.		

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
Contribute to cumulative impacts	Therefore, the impacts of the proposed project related to potential inundation by seiche, tsunami, or mudflow are considered less than significant. The proposed project would not contribute to cumulative water quality impacts. The installation of storm drain filters would improve water quality in the	No mitigation is required.	Less Than Significant
	Marina waters.	AND USE	
Physically divide an established community	The proposed project would not change the existing uses within or adjacent to the project site. The Marina is an existing recreational/open space use, which would continue with implementation of the proposed project. Therefore, the proposed project would not divide an established community or disrupt the existing physical arrangement of the surrounding area.	No mitigation is required.	Less Than Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
Conflict with any applicable land use plan, policy, or regulation of an agency with jurisdiction over the project (including, but not limited to	The proposed project would make long-term improvements to the existing land uses on site. These improvements would enhance the value of the site's	No mitigation is required.	Less Than Significant
the general plan, specific plan, local coastal program, or zoning ordinance) adopted for the purpose of avoiding or mitigating an environmental effect	existing uses and not conflict with any applicable land use plan, policy, or regulation.		
Substantially conflict with existing on-site or adjacent land uses	The land uses and intensity of uses on the project site will remain essentially the same after implementation of the Marina improvements. The only change in use involves development of the open space/habitat mitigation site, which would convert a City-owned storage area (located adjacent to Marine Stadium's northeast shore) to an eelgrass habitat mitigation area. Development of the open space/eelgrass habitat area	No mitigation is required.	Less Than Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
	would be consistent with the		
	existing low-intensity uses and		
	would complement the marine		
	environment of Marine Stadium		
	and the adjacent open space/		
	recreational uses. Therefore, no		
	conflicts with on-site or adjacent		
	land uses would occur.		
Conflict with any applicable	There are no adopted Habitat	No mitigation is required.	Less Than
habitat conservation plan or	Conservation Plans (HCPs) or		Significant
natural community	Natural Communities		
conservation plan	Conservation Plans (NCCPs)		
	applicable to the project site.		
	Therefore, the proposed project		
	would not result in effects to an		
	adopted HCP or NCCP.		
Contribute to cumulative	The proposed project is the	No mitigation is required.	Less Than
impacts	continuation of an existing use		Significant
	and would not contribute to		
	cumulative land use impacts.		

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact		Mitigation Measures ¹	Level of Significance After Mitigation
3		NOISE	3	S
Exposure of persons to or generation of noise levels in excess of standards established in the local General Plan or Noise Ordinance, or applicable standards of other agencies.	Noise associated with construction of the proposed project would result in a temporary periodic increase in existing ambient noise levels in the project area. Sensitive receptors located within 315 ft of the standard construction equipment and 706 ft of the pile driving would be exposed to noise levels in excess of the City's daytime exterior noise standard. Therefore, project-related construction activities would result in a significant	4.9-1	Prior to the issuance of any permit, the Marine Bureau Manager shall demonstrate that the following requirements are printed on all final project plans: Consistent with the City of Long Beach (City) Noise Ordinance, construction activity that produces loud or unusual noise that could impact a reasonable person of normal sensitivity shall be limited to between the hours of 7:00 a.m. and 7:00 p.m. Monday through Friday and federal holidays, and between 9:00 a.m. and 6:00 p.m. on Saturdays. No construction activities shall occur on Sundays.	Significant and Unavoidable
	noise impact that would be intermittent and temporary. These noise levels would no longer occur once construction of the project is completed.	4.9-2	Prior to the issuance of any permit, the Marine Bureau Manager shall demonstrate that the following requirement is printed on all final project plans: during construction and demolition, the project contractors shall equip all construction equipment, fixed or mobile, with properly operating and	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact		Mitigation Measures ¹	Level of Significance After Mitigation
			maintained mufflers consistent with manufacturers' standards.	
		4.9-3	Prior to the issuance of any permit, the Marine Bureau Manager shall demonstrate that the following requirement is printed on all final project plans: the project contractor shall place all stationary construction equipment so that emitted noise is directed away from sensitive receptors nearest the project site.	
		4.9-4	Prior to the issuance of any permit, the Marine Bureau Manager shall demonstrate that the following requirement is printed on all final project plans: the construction contractor shall locate equipment staging in areas that will create the greatest distance between construction-related noise sources and noise-sensitive receptors nearest the project site during all project construction.	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
		4.9-5 Prior to issuance of a grading permit, the Director of Parks, Recreation, and Marine shall hold a community preconstruction meeting in concert with the Construction Contractor to provide information regarding the construction schedule. The construction schedule information shall include the duration of each construction activity and the specific location, days, frequency, and duration of the pile driving that will occur during each phase of the project construction. Public notification of this meeting shall be undertaken in the same manner as the Notice of Availability mailings for this Draft Environmental Impact Report (EIR).	
Exposure of persons to or generation of excessive ground-borne vibration or ground-borne noise levels.	The primary source of vibration during construction would be generated by the proposed pile driving. The closest pile-driving activities to a sensitive receptor would occur during Phase 12 at a distance of 100 ft from the nearest residence. Construction	No mitigation is required.	Less Than Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
Threshold of Significance	vibration levels would exceed	Witigation Weasures	Arter Mingation
	the threshold of perception, but		
	would be below the annoyance		
	threshold, below which there is		
	virtually no risk of resulting in		
	architectural damage to normal		
	buildings. Therefore, the		
	proposed project would not		
	result in any significant		
	vibration impacts.		
A substantial permanent	The proposed project would	No mitigation is required.	Less Than
increase in ambient noise	retain the existing recreation and		Significant
levels in the project vicinity	open space uses of the project		
above levels existing without	site and would not result in		
the project.	additional noise sources.		
	Therefore, long-term operation		
	of the proposed project would		
	not result in a permanent		
	increase in ambient noise levels		
	in the project vicinity.		G1 101 1
A substantial temporary or	Noise associated with	See Mitigation Measures 4.9-1 through 4.9-5	Significant and
periodic increase in ambient	construction of the proposed	above.	Unavoidable
noise levels in the project	project would result in a		
vicinity above levels existing	temporary periodic increase in		
without the project.	existing ambient noise levels in		

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
	the project area. Sensitive	Timguron Trionbulos	THE THE SECTION
	receptors located within 315 ft		
	of the standard construction		
	equipment and 706 ft of the pile		
	driving would be exposed to		
	noise levels in excess of the		
	City's daytime exterior noise		
	standard. Therefore, project-		
	related construction activities		
	would result in a significant		
	noise impact that would be		
	intermittent and temporary.		
	These noise levels would no		
	longer occur once construction		
	of the project is completed.		
	The addition of construction		
	haul truck trips per hour to the		
	local roadways would not result		
	in a perceptible change in traffic		
	noise, and impacts related to		
	truck traffic are considered less		
	than significant.		

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

	D-44:-1 E		Level of
Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Significance After Mitigation
	-	<u> </u>	
Contribute to cumulative	Construction and operation of	No mitigation is required.	Less Than
impacts	the proposed project would not		Significant
	contribute to potential		
	cumulative impacts.		
		ICES AND UTILITIES	T
Result in substantial adverse	The proposed project is not	No mitigation is required.	Less Than
physical impacts associated	anticipated to result in an		Significant
with the provision of new or	increase in calls for police or fire		
physically altered	services or require additional		
governmental facilities or the	personnel to maintain acceptable		
need for new or physically	service ratios, response times, or		
altered governmental	other performance objectives.		
facilities, the construction of	Similarly, the project will not		
which could cause	require new or expanded police		
significant environmental	or fire facilities.		
impacts, in order to maintain			
acceptable service ratios,	The proposed project will not		
response times, or other	increase demand for or impact		
performance objectives for	capacity in the Long Beach		
public services including fire	Unified School District		
protection, police protection,	(LBUSD) and would not create a		
schools, libraries, or other	need to expand or construct new		
public facilities.	school facilities. Similarly, the		
	proposed project would not		
	result in increased demands on		

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
	the existing library facilities.		
Exceed wastewater treatment requirements of the applicable Regional Water Quality Control Board (RWQCB).	The proposed project would not exceed wastewater treatment requirements of the Los Angeles RWQCB. Impacts to wastewater infrastructure and wastewater treatment requirements are considered less than significant	No mitigation is required.	Less Than Significant
Require or result in the construction of new water or wastewater treatment facilities or expansion of existing facilities, the construction of which could cause significant environmental effects.	The proposed project includes the renovation and/or reconstruction of 13 existing restroom facilities. The new restrooms will be equipped with low-flow faucets and toilets (pursuant to Title 24 of the California Administrative Code) that would reduce the amount of water consumed by the fixtures, thereby also reducing the amount of wastewater generated when compared to existing conditions. In addition, the proposed project results in fewer slips, which may result in less demand for water	No mitigation is required.	Less Than Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
	and generation of less wastewater on site. The project would not result in a significant increase in water use or necessitate new or expanded infrastructure. In addition, project-generated wastewater will not exceed the existing capacity of the sewer delivery system and will not require the construction of new sewer delivery facilities.		
Require or result in the construction of new storm water drainage facilities or expansion of existing facilities, the construction of which could cause significant environmental effects.	The proposed project includes the replacement of existing storm drain catch basins within the parking areas, but does not create additional demands for storm water drainage. In addition, the project will not require or result in the expansion or construction of new storm water drainage facilities.	No mitigation is required.	Less Than Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
Require new or expanded water entitlements to have sufficient water supplies available to serve the project.	The new restrooms will be equipped with low-flow faucets and toilets (pursuant to Title 24 of the California Administrative Code) that would reduce the amount of water consumed by the fixtures. In addition, the proposed project results in fewer slips, which may result in less demand for water. Therefore, the proposed project will not necessitate new or expanded water entitlements, as significant increases in water demands would not result from the proposed project.	4.10-1 Prior to the issuance of building permits, the Marine Bureau Manager shall demonstrate on the final construction plans that applicable interior and exterior water conservation measures have been incorporated into all aspects of this project. At a minimum, measures shall include low-flush toilets, low-flow faucets and shower heads, and the installation of efficient irrigation systems to minimize runoff and evaporation.	Less Than Significant
Result in a determination by the wastewater treatment provider that serves or may serve the project that it has inadequate capacity to serve projected demand in addition to the provider's existing commitments.	Project-generated wastewater will not exceed the existing capacity of the sewer delivery system and will not require the construction of new sewer delivery facilities. The proposed project is not anticipated to result in a determination by the Los Angeles County Sanitation	No mitigation is required.	Less Than Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact		Mitigation Measures ¹	Level of Significance After Mitigation
Be served by a landfill with	Districts (LACSD) that inadequate capacity exists to serve the project in addition to existing commitments. Construction of the project	4.10-2	Prior to the issuance of any demolition	Less Than
insufficient permitted capacity to accommodate the project's solid waste disposal needs.	would result in solid waste that would need to be disposed of in off-site facilities. The amount of the project's construction-related solid waste would be spread out over the anticipated 6 years of construction and is not anticipated to result in a significant impact to the capacity of the off-shore disposal site (LA-2) or the land side solid waste facilities. In compliance with State Assembly Bill 939 (AB 939), the proposed project will be required to incorporate the collection of recyclable materials into project design and to require contractors to reuse construction supplies, including landscape containers,		permit, a solid waste management plan for the proposed project shall be developed by the Marine Bureau, and submitted to the Environmental Services Bureau for review and approval. The plan shall identify methods to promote recycling and reuse of construction materials as well as safe disposal consistent with the policies and programs outlined by the City of Long Beach. The plan shall identify methods of incorporating source reduction and recycling techniques into project construction and operation in compliance with State and local requirements such as those described in Chapter 14 of the California Code of Regulations and Assembly Bill (AB) 939.	Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
	where practicable or applicable to the extent feasible.		
	Long-term operation of the proposed project is not anticipated to increase the amount of solid waste generated, as the existing land uses will not change, and fewer slips may result in less generation of solid waste. Therefore, solid waste impacts due to operation of the proposed project are considered less than significant, and no mitigation is required.		
Not be in compliance with federal, State, and local statutes and regulations related to solid waste.	Solid waste generated during construction of the proposed project would not result in significant impacts related to landfill capacity or prevent compliance with federal, State, and local statutes and regulations related to solid waste. The project would comply with Assembly Bill	See Mitigation Measure 4.10-2 above.	Less Than Significant

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
	(AB) 939, which requires that		
	every city and county in		
	California implement programs		
	to recycle, reduce refuse at the		
	source, and compost waste to		
	achieve a 50 percent reduction in		
	solid waste being taken to		
	landfills.		
Contribute to cumulative	With implementation of	See Mitigation Measures 4.10-1 and 4.10-2	Less Than
impacts	Mitigation Measures 4.10-1 and		Significant
	4.10-2, the proposed project		
	would not contribute to potential		
	cumulative impacts related to		
	public services or utilities.		
	REC	CREATION	
Increase demand on the City	The primary goal of the	No mitigation is required.	Less Than
Department of Parks,	proposed project is to renovate		Significant
Recreation, and Marine's	the docks and slips, seawall,		
services and facilities	utilities, parking areas, and		
beyond its capacity, thereby	restroom facilities that are in a		
accelerating or leading to	physical state of decline, thereby		
substantial physical	extending the Marina's useful		
deterioration of existing	life and improving safety for		
recreation facilities.	recreational users. Therefore, the		
	proposed project would not		

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
	accelerate or lead to the physical		Ü
	deterioration of existing		
	recreational facilities and would		
	not increase demand on City		
	Department of Parks,		
	Recreation, and Marine services		
	and facilities beyond its		
	capacity.		
Include recreational facilities	The proposed Marina	No mitigation is required.	Less Than
or require the construction or	improvements are not		Significant
expansion of recreational	anticipated to result in any		
facilities that might have an	substantial increased use of the		
adverse physical effect on	Marina and would not adversely		
the environment.	impact other recreational		
	opportunities in the project area.		
	The proposed project includes a		
	temporary dock to accommodate		
	displaced boaters during		
	construction activities, and all		
	current customers in the Marina		
	will continue to have a slip once		
	the proposed project is		
	implemented. Therefore, the		
	proposed project would not		
	require the construction or		

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact		Mitigation Measures ¹	Level of Significance After Mitigation
	expansion of additional			
	recreational facilities, and			
	impacts to these facilities are considered less than significant.			
Contribute to cumulative	The proposed project would not	No mitio	ation is required.	Less Than
impacts	contribute to potential	1 to ming	ation is required.	Significant
Impacts	cumulative impacts related to			Significant
	recreational facilities.			
	TRAFFIC A	ND CIRC	ULATION	
Cause an increase in traffic	The proposed project would	4.12-1	Prior to the issuance of demolition or	Less Than
which is substantial in	result in fewer boat slips, and		building permits, the City of Long	Significant
relation to the existing traffic	therefore no increase or		Beach (City) shall develop a	
load and capacity of the	significant change in operational		Construction Traffic Management Plan	
street system (i.e., result in a	traffic levels is expected.		for review and approval by the City of	
substantial increase in either			Long Beach Traffic Engineer. The plan	
the number of vehicle trips,	Although the proposed project		shall be designed by a registered Traffic	
the v/c ratio on roads, or	itself would not generate new		Engineer and shall address traffic	
congestion at intersections).	vehicle trips, there would be a		control for any street closure, detour, or	
	temporary increase in traffic		other disruption to traffic circulation and	
	volumes during construction		public transit routes. The plan shall	
	activities. Construction workers		identify the routes that construction	
	will add 64 daily passenger car		vehicles will use to access the site, the	
	trips (32 inbound in the morning		hours of construction traffic, traffic	
	and 32 outbound in the evening)		controls and detours, and off-site vehicle	
	to each phase of the project, but		staging areas. The plan shall also restrict	

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
Threshold of Significance	will not add a.m. or p.m. peakhour trips to construction traffic because the workers will arrive on site before the 7:00 a.m.—9:00 a.m. peak period and will depart prior to the 4:00 p.m.—6:00 p.m. peak period. A total of 118 trucks are expected during the typical 6-month (26-week) construction phase, resulting in an average of 4—5 trucks per week. Therefore, an average of one truck per day (2 truck trips, equal to 4 passenger car equivalent [PCE] trips), with a maximum of one truck trip (2 PCE) during the a.m. peak hour, is estimated to occur during a typical construction phase. Construction-related vehicle trips associated with Phase 1A (the open space/habitat	construction trucks to no more than 19 during the a.m. peak hour for any one phase of the project, prohibit truck trips after 3:30 p.m., and require that a minimum of one travel lane in each direction on Marina Drive and 2nd Street be kept open during construction activities. The plan shall also require the City to keep all haul routes clean and free of debris including, but not limited to, gravel and dirt.	After Mitigation

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
Threshold of Significance	mitigation site) are estimated to	Wittigation Weastifes	Atter Willigation
	total 585 truckloads over a		
	duration of 1.5 months. This		
	would result in an average of		
	approximately 18 trucks per day		
	(36 truck trips [72 PCE]), with a		
	maximum of 9 trucks (18 truck		
	trips [36 PCE]) in the a.m. peak		
	hour.		
	A total of 836 trucks each are		
	expected during Phases 2 and 3,		
	resulting in an average of 7		
	trucks per day (14 truck trips [28		
	PCE]) occurring in the a.m.		
	peak-hour period for each of		
	these phases.		
	The total daily construction-		
	related trips are expected to be		
	less than significant with		
	implementation of a		
	Construction Traffic		
	Management Plan.		

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
Exceed, either individually	Phases 1/1A will be		Less Than
or cumulatively, a LOS	implemented concurrently.		Significant
standard established by the	Based on the estimated trip		
county congestion	generation, the construction		
management agency for	activity during Phases 1/1A will		
designated roads or	add approximately 140 daily		
highways.	PCE trips and result in the most		
	intense trucking phase of the		
	project. The truck trips		
	associated with Phases 1/1A		
	would travel two separate routes		
	leaving the project area. Trucks		
	associated with Phase 1 (Basin		
	4) would utilize Appian Way,		
	2nd Street, and Studebaker Road		
	to State Route 22 (SR-22).		
	Trucks associated with Phase 1A		
	would utilize Eliot Street,		
	Colorado Street, Park Avenue,		
	and Seventh Street to SR-22.		
	Delivery trucks coming to the		
	project site would travel via		
	Studebaker Road, 2nd Street,		
	and Marina Drive.		

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
	The addition of 68 daily PCE		
	associated with Phase 1 is		
	expected to be insignificant to		
	traffic flows along Appian Way,		
	2nd Street, and Studebaker		
	Road. The 72 daily PCE of		
	Phase 1A are also expected to be		
	insignificant to traffic flows		
	along Eliot Street, Colorado		
	Street, Park Avenue, and 7th		
	Street. Therefore, the total daily		
	construction-related trips on area		
	roadways are expected to be less		
	than significant with		
	implementation of a		
	Construction Traffic		
	Management Plan.		
Result in inadequate parking	The overall number of spaces	No mitigation is required.	Less Than
capacity.	provided at project completion		Significant
	exceeds the City's requirements		
	by 1,289 spaces, including the		
	addition of 23 Americans with		
	Disabilities Act (ADA)		
	accessible parking spaces. No		
	impacts related to parking would		

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
	occur with implementation of	-	
	the proposed project.		
Substantially increase	The proposed project would not	No mitigation is required.	Less Than
hazards due to a design	result in any significant impacts		Significant
feature (e.g., sharp curves or	related to hazardous design		
dangerous intersections) or	features.		
incompatible uses (e.g., farm			
equipment)			
Result in a change in air	The proposed project would not	No mitigation is required.	Less Than
traffic patterns, including	result in any significant impacts		Significant
either an increase in traffic	related to air traffic patterns.		
levels or a change in location			
that results in substantial			
safety risks			
Result in inadequate	The proposed project would not	No mitigation is required.	Less Than
emergency access	result in any significant impacts		Significant
	related to emergency access.		
Conflict with adopted	The proposed project would not	No mitigation is required.	Less Than
policies, plans, or programs	result in any significant impacts		Significant
supporting alternative	related to adopted policies,		
transportation (e.g., bus	plans, or programs supporting		
turnouts, bicycle racks)?	alternative transportation.		

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact		Mitigation Measures ¹	Level of Significance After Mitigation
Contribute to cumulative	There is the potential for	4.12-2	Prior to the issuance of demolition or	Less Than
impacts	construction of the proposed		building permits, the Marine Bureau	Significant
	project and construction for the		Manager shall, under the direction of the	
	Home Depot Project and/or the		City of Long Beach Traffic Engineer,	
	Second+PCH Project to occur at		address the truck route and circulation	
	the same time. Therefore, should		effects of the Home Depot and/or the	
	either the Second+PCH Project		Second+PCH Project construction,	
	or the Home Depot Project be		should either of these projects be under	
	under construction at the same		construction in the vicinity of the project	
	time as the proposed Marina		site during construction of the Alamitos	
	Rehabilitation Project, a		Bay Marina Rehabilitation project. The	
	construction traffic control		coordination shall identify the	
	measure requiring the City of		construction routes, the hours of	
	Long Beach Traffic Engineer to		construction traffic, traffic controls and	
	address the truck route and		detours, and off-site vehicle staging	
	circulation effects of		areas, and address traffic control for any	
	construction traffic associated		street closure, detour, or other disruption	
	with these cumulative projects is		to traffic circulation and public transit	
	warranted to ensure that		routes.	
	potential cumulative			
	construction traffic is addressed.			
	With implementation of this			
	measure, the project's			
	contribution to cumulative			
	traffic impacts is considered less			

Table 1.A: Summary of Project-Specific Impacts, Mitigation Measures, and Level of Significance

Threshold of Significance	Potential Environmental Impact	Mitigation Measures ¹	Level of Significance After Mitigation
	than cumulatively significant.		
	The project would not contribute		
	to long-term operational		
	cumulative traffic impacts.		