

IRRIGATION SYMBOLS

Backflow Preventer Assembly -----	
Controller -----	
Electrical Conduit -----	
Pipe:	
Existing City Main Line -----	
Pressure Main Line -----	
Lateral Line -----	
Point of Connection -----	POC
Electrical Service Control Cabinet -----	
Pull Box -----	<input type="checkbox"/> PB
Station Designation (Remote Control Valve) -----	<p>4.0 — Liters/second</p> <p> — Station</p> <p>65 — Valve size, mm</p> <p>60.5 — GPM</p> <p> — Station</p> <p>2.5" — Valve size</p>
Gate Valve -----	
Quick Coupler -----	<input type="checkbox"/>
Remote Control Valve -----	
Water Meter -----	WM

Dimensions are in millimeters, except as noted

REVISIONS		CITY OF LONG BEACH, CALIFORNIA DEPARTMENT OF PUBLIC WORKS	STANDARD PLAN NO.	
NO.	DATE		METRIC <b>401</b>	
	12/23/02	<b>IRRIGATION SYMBOLS</b>	SHEET	
			1 OF 1	
			APPROVED BY: <i>Mark Christoffel</i>	DATE: <u>1/10/03</u>
			CITY ENGINEER R.E. No. <u>40569</u>	EX. DATE: <u>03/31/03</u>